

Categorie	Betreft	Vraag	Antwoord
Eisen en criteria	verduidelijkingsvraag: 4.1 Storage 10	Om hoeveel AFP clients gaat het?	575 Endpoints
Eisen en criteria	verduidelijkingsvraag: 4.1 Storage 10	Is de aanbestedingsdienst zich ervan bewust dat de AFP protocollen in de toekomst niet meer ondersteund worden door Apple terwijl de oplossingen een gegarandeerde support moeten leveren aan de releases van de besturingsystemen?	Ja, daar zijn we ons van bewust.
Eisen en criteria	1.2.2	De 10GbE endpoints gaan die op glas of koper uitgevoerd worden?	Koper.
Eisen en criteria	1.2.2	Gaat de huidige infrastructuur gebruikt worden of gaat er een nieuwe bekabeling getrokken worden tussen diverse locaties?	Ja, bij voorkeur tussen de MER's en de SER's.
Eisen en criteria	1.2.2 Omvang van de aan te besteden opdracht	Er wordt gesproken over 575 endpoints die gelijktijdig kunnen werken op het high speed storage systeem met minimale bandbreedte van 80%. Wordt hiermee het netwerk intern bedoeld of van de storage naar endpoint.	Van storage naar endpoint
Bestek/beschrijvend document	Nota Van Inlichtingen, vraag 47	Dient er een volledig nieuw 10GbE end to end netwerk geleverd te worden voor alle 575 endpoints in het netwerk?	Nee.
Bestek/beschrijvend document	Nota van Inlichtingen, Vraag 26	Wat is de verhouding van de gevraagde bandbreedte ten opzichte van de vereiste throughput die het high speed media storage systeem moet leveren?	Inschrijver moet zorgdragen dat de 575 endpoints gelijktijdig kunnen werken op het high speed media storage systeem, waarbij ieder endpoint gebruik maakt van een 10GbE netwerk connectie en hierbinnen de minimale constante bandbreedte van 80% kan benutten.
Bestek/beschrijvend document	Installatie (Pls note questions in English)	<ul style="list-style-type: none"> o A/C present ? Enough for adding our system? o Technical floor or ceiling cable path? o Rack : understood the existing racks are branded Minkels § Can we use different brand or Minkels is mandatory? § Can we have rack spec : Size, depth, etc ... ? · A site survey may be required? o Site : is there different sites/building? Main and backup site? What is EIA & SER? “In the contract the necessary network should be included (ie switches) and cabling within and between the EIA and SER areas as well as expand the server-racking, emergency and back-up facilities.” o What is the “link” (if any) between legacy system and the new system? “The new storage solution must be in addition to the existing infrastructure in EIA 1 built up. It should the contractor indicate in the tender the minimum specifications in terms of rack space, power and cooling.” o UPS : are we sure we want to supply a UPS system that supplies battery backup to our system in the event of a power failure??? “ The Contractor must provide for the award of a sufficient UPS system in favor of the total available storage solution, and which is consistent with the current situation.” 	<ul style="list-style-type: none"> o A/C present ? Enough for adding our system? Aircondition volstaat o Technical floor or ceiling cable path? Plafond kabelgoten aanwezig o Rack : understood the existing racks are branded Minkels § Can we use different brand or Minkels is mandatory? Nee, Minkels is verplicht § Can we have rack spec : Size, depth, etc ... ? Het huidige Main Equipment Room (MER) is uitgevoerd met 8 rackunits van het merk Minkels. Deze hebben de afmeten van 22000x800x1000 MM (HxBxD) en een inhoud van 46 Units (U). · A site survey may be required? Is niet gewenst. o Site : is there different sites/building? Main and backup site? What is EIA & SER? Nee. EIA is de Main Equipment Room (MER) SER is de Switch Equipment Room (SER) “In the contract the necessary network should be included (ie switches) and cabling within and between the EIA and SER areas as well as expand the server-racking, emergency and back-up facilities.” o What is the “link” (if any) between legacy system and the new system? Geen link. Er is geen bestaande storage oplossing. “The new storage solution must be in addition to the existing infrastructure in EIA 1 built up. It should the contractor indicate in the tender the minimum specifications in terms of rack space, power and cooling.” o UPS : are we sure we want to supply a UPS system that supplies battery backup to our system in the event of a power failure??? Ja. “ The Contractor must provide for the award of a sufficient UPS system in favor of the total available storage solution, and which is consistent with the current situation.”