

ELECTRICAL GROUNDING, BONDING AND CONNECTIVITY PRODUCTS

FEATURED PRODUCTS




ERICO ERICONTACT Double Rail Contact – DSK1912 (715060)



The ERICO ERICONTACT series of rail contacts provides a superior quality connection to the rail web with a very low contact resistance. The contacts are quickly and easily fitted by means of an insertion tool, regardless of weather conditions. All ERICO ERICONTACT components are manufactured according to high standards and norms. Tested to the most demanding requirements of the Rail Industry Standards, ERICO ERICONTACT is the ideal solution for mechanically applied connections such as signal engineering, earthing (grounding), or traction return current.

The ERICO ERICONTACT Double Rail Contact series offers connections on both sides of the rail web. This is a significant advantage when making interconnections in the station area, for example. The ERICO ERICONTACT Double Contact is ideal solution in confined spaces. With a clearance of only 50 mm between the rail heads, the ERICO ERICONTACT can still be inserted and the cable lug connected from both sides.

- Easy to install
- Very low contact resistance ($< 5 \mu\Omega$)
- Same electrical resistance on the two sides of the contact
- The contact surface of the two copper bushes is made inside the rail



Part Number	DSK1912
Article Number	715060
Rail Web Thickness	12,0 – 13,4 mm
Rail Type	AS41 BHP42 RI59 RI60 S41
Drill Hole Diameter (Ø)	19 mm
Screw Diameter (Sc)	M12
Screw Length (L)	60 mm
Washer Inner Diameter	13 mm
Washer Outer Diameter	24 mm
Nut Material	Stainless Steel 304

Part Number	DSK1912
Standard Packaging Quantity	1 pc
UPC	78285688020
EAN-13	8711893016451

Kit includes: (1) hex-head stainless steel 304 bolt, (1) electrolytically tin-plated copper bush set (2 parts), (2) stainless steel 304 round washers, and (1) hexagonal stainless steel 304 nut or (1) electroplated steel nut (depending on contact type).
The washer and nut for DSK13518 are integrated into one piece.


ERICO ERICONTACT Double Rail Contact – DSK1914 (715055)



The ERICO ERICONTACT series of rail contacts provides a superior quality connection to the rail web with a very low contact resistance. The contacts are quickly and easily fitted by means of an insertion tool, regardless of weather conditions. All ERICO ERICONTACT components are manufactured according to high standards and norms. Tested to the most demanding requirements of the Rail Industry Standards, ERICO ERICONTACT is the ideal solution for mechanically applied connections such as signal engineering, earthing (grounding), or traction return current.

The ERICO ERICONTACT Double Rail Contact series offers connections on both sides of the rail web. This is a significant advantage when making interconnections in the station area, for example. The ERICO ERICONTACT Double Contact is ideal solution in confined spaces. With a clearance of only 50 mm between the rail heads, the ERICO ERICONTACT can still be inserted and the cable lug connected from both sides.

- Easy to install
- Very low contact resistance ($< 5 \mu\Omega$)
- Same electrical resistance on the two sides of the contact
- The contact surface of the two copper bushes is made inside the rail



Part Number	DSK1914
Article Number	715055
Rail Web Thickness	13,5 – 15,5 mm
Rail Type	100 lb ARAB 85 lb ASCE AS50 NP46 S49
Drill Hole Diameter (Ø)	19 mm
Screw Diameter (Sc)	M12
Screw Length (L)	60 mm
Washer Inner Diameter	13 mm
Washer Outer Diameter	24 mm
Nut Material	Electroplated Steel

Part Number	DSK1914
Standard Packaging Quantity	1 pc
UPC	78285659838
EAN-13	8711893016420

Kit includes: (1) hex-head stainless steel 304 bolt, (1) electrolytically tin-plated copper bush set (2 parts), (2) stainless steel 304 round washers, and (1) hexagonal stainless steel 304 nut or (1) electroplated steel nut (depending on contact type).
The washer and nut for DSK13518 are integrated into one piece.

WARNING

Pentair products shall be installed and used only as indicated in Pentair's product instruction sheets and training materials. Instruction sheets are available at erico.pentair.com and from your Pentair customer service representative. Improper installation, misuse, misapplication or other failure to completely follow Pentair's instructions and warnings may cause product malfunction, property damage, serious bodily injury and death and/or void your warranty.

© 2016 Pentair All rights reserved

Pentair, CADDY, CADWELD, CRITEC, ERICO, ERIFLEX, ERITECH and LENTON are owned by Pentair or its global affiliates.

All other trademarks are the property of their respective owners. Pentair reserves the right to change specifications without prior notice.