



Fabrikant	Philips	Leverancier		
Gewicht	6,85	Kleur : Lichtgrijs		
Aantal lampen	1	Artikelnummer		
Lamptype 1	LED GRN25/830 3000K			
Lamptype 2				
Lamptype 3				
IP- klasse	66	Slagvastheidsklasse	Aansluitwaarde	21,3
Gewicht	6,85	Vervangend armatuur		
Dimbaar	avond/nacht	<input checked="" type="checkbox"/>	Dimmer	

Overige info:

Product family code:	BGP501 - Iridium gen4 Mini	Leadtime:	9 weeks
Housing configuration:	HSR - With SystemReady components	Brand:	PHL - Philips
Product family code extension:	N - No CityTouch	Mounting device:	SP - Spigot (no cable)
Protection class:	I - Safety Class I	Surge Protection:	STD - Standard surge
Optics:	DM50 - Distribution medium DM50	Product family:	BGP501 - Iridium gen4 Mini
LED version:	4S - Ledgine O	Housing color:	SI - RAL 9006
Optic element:	N - No Louver	Colored Part:	AL - All luminaire painted
Ambient Temperature:	T35 - Ta = 35°C (Outdoor)	RAL color:	9006 - White aluminum
Consumption line:	LED - Ledgine O	Other color choice:	NA - Not applicable
Light source color:	830 - Warm White 3000K	Coating:	STD - Standard protection
LED family code:	LED24 - 2400 Lumens	Fuse:	N - No fuse
Driver:	PSD-SR - PSU with DALI and SystemReady	Safety Device:	N - No safety strap
Light Regulation:	D11 - Line Switch through switch OFF	GR_HOUSCONF:	NANO
Lighting control unit:	CLO - Constant Light Output	Optical cover:	FG - Flat glass/extra clear
Number of leds:	20	Gearplate:	GF - With Gearflex
Driver code:	37_0_0 - 37_0_0	Lighting effects:	N - No diffusing effect
Driver Program:	8VFVVPJ0C4A1	Cover Clip :	N - Standard glass fixation
Special Project:	. - No special project		
Packaging:	CT - Carton box		
Top sensor:	SRT - SR Socket on TOP (with cap)		
Network ID:	NA - Not applicable		
Photocell programming:	NA - Not applicable		
Bottom sensor:	N - No socket/device		
System Ready Interface:	SRTB - SR Socket		
Supply cable type:	N - No Cable		