


The diagram illustrates a multi-lane road design with several key features:

- Trottoir (Left Side):**
 - betontegels 300x300x45 mm
 - op 50mm straatzand
- Kantopsluiting (Right Side):**
 - trottoirband 180/200x250 mm
 - steunrug van beton c12/15 (0.05 m³/m)
- Goottegel:**
 - goottegel 150x300x70 mm
- Lichtmast h=10m:** Located near the first crossing.
- Hekwerk openbare ruimte h=1.50m:** Public space fence height.
- Busbaan pendelbus:**
 - asfalt 140mm:
 - 35mm AC 11 DL-B
 - 45mm AC 16 TL-B
 - 60mm AC 22 OL-B
 - menggranulaat 250mm
 - zandbed 300mm
- Parkeervakken:**
 - asfalt 115mm:
 - 35mm AC 11 DL-B
 - 80mm AC 22 OL-B
 - menggranulaat 250mm
 - zandbed 300mm
- Parkeerweg:**
 - asfalt 115mm:
 - 35mm AC 11 DL-B
 - 80mm AC 22 OL-B
 - menggranulaat 250mm
 - zandbed 300mm
- Looppad:**
 - asfalt 115mm met rode coating:
 - 35mm AC 11 DL-B
 - 80mm AC 22 OL-B
 - menggranulaat 250mm
 - zandbed 300mm
- Parkeervakken:**
 - asfalt 115mm:
 - 35mm AC 11 DL-B
 - 80mm AC 22 OL-B
 - menggranulaat 250mm
 - zandbed 300mm
- Invaliegrif:** Indicated by a red dashed line labeled "Invaliegrif".
- Lichtmast h=6m:** Light pole height in the middle section.
- Parkeervakken:**
 - asfalt 115mm:
 - 35mm AC 11 DL-B
 - 80mm AC 22 OL-B
 - menggranulaat 250mm
 - zandbed 300mm
- Lichtmast h=4m:** Light pole height towards the right side.
- Kantopsluiting:**
 - trottoirband 180/200x250 mm
 - steunrug van beton c12/15 (0.05 m³/m)
- Goottegel:**
 - goottegel 150x300x70 mm
- Lichtmast h=10m:** Another light pole location further right.
- Nieuwe verbinding tussen bestaande greppels:**
 - beton Ø300 mm
 - b.o.b. n.t.b.+
- Troottierregels 300x300x45mm - grijs:** Grey concrete curb rules.
- Hekwerk luchtvaartterrein h=2.70m:** Airfield fence height at the far right.



2.0									
1.0	Eerste uitgave			Rv01B	JRv01B	Rv01B	Rv01B	08-09-2023	
versie	omschrijving			getekend	gecontroleerd	afgekeurd		datum	
opdrachtgever									
Maastricht Aachen Airport									
project					 Royal HaskoningDHV <i>Enhancing Society Together</i> HaskoningDHV Nederland B.V. Mobility & Infrastructure				
Parkeerplaats zuid P7									
omschrijving									
Normaalprofiel NP 1 incl. details					documentstatus DEFINITIEF BESTEK documentversie 1.0				
formaat	schaal	fase		bladnr.					
A1	1:200	BO		1	1	projectnummer BG8108-100-100-200A			