

1 Site to Site IPSEC VPN configuration

General Details	
Date	
Change / Project	

Contact Details	Site A	Site B
Company Name	Gemeente Lelystad	
Technical Contact	Martijn Daling / Roy Lachman	
Technical Contact Phone	06-11706831 / 06-36126118	
Technical Contact E-Mail	rjm.daling@lelystad.nl r.lachman@lelystad.nl	

Hardware Details	Site A	Site B
Firewall Make	CheckPoint	
Firewall Model	SG6600	
Firewall OS Version	R80.40	

Phase 1 Settings	Site A	Site B
IKE Initiator Mode	IKEv2	
Authentication Method	Pre-Shared Secret	
Encryption Algorithm	AES256-CBC	
Hash Algorithm	SHA256	
ISAKMP SA Lifetime	28800 Seconds	
Diffie-Hellman Key Group	DH Group 14	
Gateway IP Address	193.105.33.111	
Identity	193.105.33.111	

Phase 2 Settings	Site A	Site B
IPSec Security Protocol	ESP	
Encryption Algorithm	AES256-CBC	
Hash Algorithm	SHA256	
IPSEC SA Lifetime	3600 Seconds	
IPSEC SA Lifesize	0 KByte	
Perfect Forwarding Secrecy	DH Group 14	
Local / Remote Network		

Ports	Site A	Site B
Service		
Portnumber(s)		