

Technical drawing of a bent pipe assembly. The main view shows a pipe with a vertical section of 1200 mm and a horizontal section of 300 mm, with a total length of 1500 mm. The bend angle is 70°. The pipe has a diameter of 60.3 mm and a wall thickness of 2.9 mm. The bend radius is R=275 mm. A side view shows the pipe's profile with a 5° angle and a vertical dimension of 1150 mm.