

Spoorstaafprofiel	Staalkwaliteit	Materiaalnummer	Type spoorstaaf	Vigerende norm	Hardheid (HBW)	Yield Stress R _{p0.2} min. (MPa)	Tensile Strength R _m min. (MPa)
60R2	R200	1.0521	groefrail standaard	NEN-EN 14811:2019	200-240	350	680
53R1	R200	1.0521	groefrail laag	NEN-EN 14811:2019	200-240	350	680
73C1	R220 G1	1.0604	volkopgroefrail	NEN-EN 14811:2019	220-260	430	780
105C1	R220 G1	1.0604	"Dicksteg" constructierail	NEN-EN 14811:2019	220-260	430	780
310C1	R220 G1	1.0604	hartstukblok constructierail	NEN-EN 14811:2019	220-260	430	780
49E1	R260	1.0623	vignoleraail	NEN-EN 13674-1:2011+A1:2017	260-300	470	880
120x85	S690QL	1.8928	gefreesde blokrail	NEN-EN 10025	200-260	690	770