

Drumtainer



Materials Handling Products

- Mobile overpack for standard drums (200–230 litres)
 - With integrated spill containment
 - Easy and efficient handling
-
- Mobil overpakning for standardtromle (200–230 l)
 - Integreret spildopsamling
 - Nem og effektiv håndtering

For more efficient and easy handling of drums

The Drumtainer is an innovative overpack, which has been developed for convenient transportation, storage and handling of drums with volumes of 200–230 litres. Whether detergents or chemicals – with the Drumtainer you will provide to your customer not only a very safe, but also a very efficient way of supplying your products.

It is the large castors, the spacious handgrips and the push bars which make the Drumtainer convenient to handle by hand. Lifting and transporting the Drumtainer by fork lift truck is also possible. And the integrated spill containment function replaces the need of a space consuming separate spill containment and with that the wearisome lifting of the drum onto the spill containment.

The non-corrosive Drumtainer is hygienic. The drum is positioned slightly tilted in the Drumtainer which facilitates an almost completely emptying of the drum by pump. Hence there will be less remains in the drum and therefore less cleaning is required. The special trailer version allows multiple Drumtainers to be connected and transported. In addition the design of the Drumtainer will support the professional image of your company.



The trailer version can be connected to each other.

Trailer-versionen af Drumtainer muliggør transport af flere tromler.



The drum is protected against rain and dirt.

Drumtainer er beskyttet mod regn og snavs.

Til effektiv og nem håndtering af tromler

Drumtainer er en innovativ overpakning, som er udviklet til praktisk transport, oplagring og håndtering af tromler med volumen på 200–230 l. Uanset om det drejer sig om rengøringsmidler eller kemikalier kan du med Drumtainer ikke blot give din kunde en sikker, men også en meget effektiv måde at levere dine produkter på.

Drumtaineren har store drejehjul, rummelige håndgreb og skubbestænger, som gør den praktisk at betjene med håndkraft. Det er også muligt at løfte og transportere Drumtainer med en gaffeltruck. Den integrerede spildopsamling fjerner behovet for en pladskrævende spildbeholder og arbejdskrævende løft af tromlen op til spildbeholderen.

Drumtainer korroderer ikke og er hygiejnisk. Tromlen placeres med et let vip i Drumtainer, som tømmer den næsten helt ved hjælp af en pumpe. Dette giver færre rester i tromlen, og derfor et mindre behov for rengøring. Konstruktionen af Drumtainer gør det muligt at forbinde og transportere flere styk ad gangen. Hertil kommer også, at designet af Drumtainer støtter din virksomheds professionelle image.



Multiple drums can be transported at the same time.

Note: Maximum load to be put behind Drumtainer 700 kg.

Flere tønder kan transporteres samtidig.

Bemærk: Maksimumsbelastningen 700 kg skal ligge bag Drumtainer.



The lid has openings on the side to allow connection of hoses even when lid is closed.

Låget er forsynet med åbninger i siden, så der nemt kan tilsluttes slanger, selv når låget er lukket.

The advantages in a nut shell

- Made of impact resistant, non-corrosive material.
- Fits all standard drums (plastic and steel) with a volume of 200-230 litres.
- Product sizes adapted to pallets, doors and elevators.
- Protective Drumtainer prolongs lifetime of the drum.
- 1°-tilted position of drum in Drumtainer supports emptying of contents by pump.
- To handle product with a specific mass of up to 1.5.
- Integrated spill containment for optimal safety.
- Drums are easy to enter into or remove from the Drumtainer.
- Hygienic, easy to clean.
- DIBT-approval applied for.
- Possibility to add labels with company logo, product information or safety stickers.
- Large area for user instructions on the inside of the lid.
- Attractive design.

Fordelene i en nøddeskal

- Fremstillet af slagfast, ikke-korroderende materiale.
- Passer til alle standardtromler (plastik og stål) med volumen på 200-230 l.
- Produktstørrelser tilpasset til paller, døre og elevatorer.
- Den beskyttende Drumtainer forlænger tromlens levetid.
- 1°- vippe stilling af tromlen i Drumtainer muliggør udtømning af indholdet med pumpe.
- Håndtering af produkter med en vægtfylde op til 1,5.
- Integreret spildcontainer for optimal sikkerhed.
- Det er nemt at isætte og udtage tromler fra Drumtainer.
- Hygiejnisk, nem at rengøre.
- Der er ansøgt om DIBT-godkendelse.
- Mulighed for påsætning af mærkater med firmalogo, produktinformation eller sikkerhedsmærkater.
- Brugsanvisninger på ydersiden.
- Attraktivt design.

Technical details | Specifikationer

Type	Drumtainer
Length (in mm) Længde (i mm)	800
Width (in mm) Bredde (i mm)	600
Height (in mm) Højde (i mm)	1360
Volume (in liters) Volumen (i liter)	400
Weight (in kg) Vægt (i kg)	34 (Trailer version: 37 Version wagon: 37)
Max. load (in kg) Maks. last (i kg)	300



The slots on the side allow lifting and transporting by fork lift trucks.
Åbningerne i siden muliggør løft og transport med gaffeltruck.



The inside of the lid stores a drum closure tool for drum cap.
Indersiden af låget har oplagringsplads til tromleværktøj.



A drumlift can be used to place the drum easy and safe into the Drumtainer.
En løfteanordning kan bruges til at placere tønden nemt og sikkert i Drumtainer.

Efficient, safe and easy to handle | Effektiv, sikker og nem at håndtere

Trailer version Version wagon

Openings for connection hoses

Åbninger for tilslutning af slanger

Space for product information

Plads for produkt-information

Instructions for use

Plads til sikkerhedsmærkater

Slots for fork lift truck

Åbninger til gaffeltruck

Trailer version (optional)

Version wagon



Standard version

Lid for protection against rain and dirt

Låg til beskyttelse mod støv og regn

Drum closure tool for drum cap

Opbevaringssted for værktøj for låg

Space for product information

Plads for produkt-information

Spacious handgrips
Rummelige håndgreb

Rigid, easy to clean material

Stift materiale, der er nemt at rengøre

Large castors
Store drejehjul

Swivel castors with brakes
Drejehjul med bremser

