



Zone 28 v2 722191 | Groningen ZP-CAES Systeem, 53.24304069572769, 6.687871594668537

Report

Project Name	722191 Groningen ZP-CAES Systeem
Project Address	53.24304069572769, 6.687871594668537
Prepared By	Pondera Consult w.pustjens@ponderaconsult.com

System Metrics	
Design	Zone 28 v2
Module DC Nameplate	14.9 MW
Inverter AC Nameplate	9.98 MW Load Ratio: 1.49
Annual Production	12.58 GWh
Performance Ratio	84.3%
kWh/kWp	844.7
Weather Dataset	Groningen ZP (TMY), Groningen ZP, ECMWF/ERA (custom)
Simulator Version	a71278e7b0-da8e8f0c4a-a9a24f339a-59a9e93b78

Project Location



⚡ Annual Production			
	Description	Output	% Delta
Irradiance (kWh/m²)	Annual Global Horizontal Irradiance	1,014.9	
	POA Irradiance	1,002.4	-1.2%
	Shaded Irradiance	990.2	-1.2%
	Irradiance after Reflection	944.8	-4.6%
	Irradiance after Soiling	926.0	-2.0%
	Total Collector Irradiance	925.9	0.0%
Energy (kWh)	Nameplate	13,788,414.4	
	Output at Irradiance Levels	13,555,432.0	-1.7%
	Output at Cell Temperature Derate	13,501,893.9	-0.4%
	Output After Mismatch	12,887,115.1	-4.6%
	Optimal DC Output	12,837,256.5	-0.4%
	Constrained DC Output	12,808,516.9	-0.2%
	Inverter Output	12,640,349.0	-1.3%
	Energy to Grid	12,577,147.0	-0.5%
Temperature Metrics			
Avg. Operating Ambient Temp		13.2 °C	
Avg. Operating Cell Temp		18.5 °C	
Simulation Metrics			
Operating Hours			4171
Solved Hours			4171

☁ Condition Set												
Description	Groningen PVGIS-SARAH2 (TMY)											
Weather Dataset	Groningen ZP (TMY), Groningen ZP, ECMWF/ERA (custom)											
Solar Angle Location	Meteo Lat/Lng											
Transposition Model	Perez Model											
Temperature Model	Sandia Model											
Temperature Model Parameters	Rack Type	a	b	Temperature Delta								
	Fixed Tilt	-3.56	-0.075	3°C								
	Flush Mount	-2.81	-0.0455	0°C								
	East-West	-3.56	-0.075	3°C								
	Carport	-3.56	-0.075	3°C								
Soiling (%)	J	F	M	A	M	J	J	A	S	O	N	D
	2	2	2	2	2	2	2	2	2	2	2	2
Irradiation Variance	5%											
Cell Temperature Spread	4° C											
Module Binning Range	-2.5% to 2.5%											
AC System Derate	0.50%											
Module Characterizations	Module		Uploaded By		Characterization							
	JAM72S30-550/MR (1500V) (JA Solar)		HelioScope		Spec Sheet Characterization, PAN							
Component Characterizations	Device			Uploaded By		Characterization						
	SUN2000-185KTL-H1 (@40C) (2021) (Huawei)			HelioScope		Spec Sheet						

📦 Components		
Component	Name	Count
Inverters	SUN2000-185KTL-H1 (@40C) (2021) (Huawei)	57 (9.98 MW)
Strings	10 AWG (Copper)	1,026 (117,834.6 m)
Module	JA Solar, JAM72S30-550/MR (1500V) (550W)	27,072 (14.9 MW)

🔌 Wiring Zones			
Description	Combiner Poles	String Size	Stringing Strategy
Wiring Zone	-	13-27	Along Racking

🏠 Field Segments									
Description	Racking	Orientation	Tilt	Azimuth	Intrarow Spacing	Frame Size	Frames	Modules	Power
Zone 28	East-West	Landscape (Horizontal)	15°	310°	2.5 m	6x12	188	27,072	14.9 MW

Detailed Layout

