

Bijlage 16 – Eisen emissieklasse voertuigen (13-08-2024)

	Periode 1	Periode 2	Periode 3	Periode 4
	2023-2024	2025-2027	2028-2029	2030 en verder
Licht (‘minimaterieel’) (<19 kW)	geen eis	geen eis	100% ZE	100% ZE
Zeer licht (19-37 kW)	stage IIIa (Shovel) Geen eis (Tractoren)	stage IIIa (Shovel) Geen eis (Tractoren)	stage IIIa (Shovel) stage IIIa (Tractoren)	stage IIIa (Shovel) stage IIIa (Tractoren)
Licht (37-56 kW)	stage IIIb (Shovel) Geen eis (tractoren)	stage IIIb (Shovel) Geen eis (tractoren)	stage IIIb (Shovel) stage IIIb(Tractoren)	stage IIIb (Shovel) stage IIIb (Tractoren)
Middelzwaar materieel (56-130 kW) Shovel/Tractoren	stage IIIb (Shovel) Geen eis (tractoren)	stage IIIb (Shovel) Geen eis (tractoren)	Stage V of IV met roetfilter (Shovel) stage IIIb (Tractoren)	Stage V of IV met roetfilter 100% ZE (2035) (Shovel) stage IIIb (Tractoren)
Zwaar materieel (130-560kW) Shovel/Tractoren	stage IIIb (Shovel) Geen eis (tractoren)	stage IIIb (Shovel) Geen eis (tractoren)	Stage V of IV met roetfilter (Shovel) stage IIIb (Tractoren)	Stage V of IV met roetfilter 100% ZE (2035) (Shovel) stage IIIb (Tractoren)
Zeer zwaar materieel (>560kW) Specialistisch materieel (levensduur >15 jaar) Shovel/Tractoren	stage IIIb (Shovel) Geen eis (tractoren)	stage IIIb (Shovel) Geen eis (tractoren)	Stage V of IV met roetfilter (Shovel) stage IIIb (Tractoren)	Stage V of IV met roetfilter 100% ZE (2035) (Shovel) stage IIIb (Tractoren)
N1 – Bestelbusjes M1 – Personenvervoer	EURO 5	EURO 5	100% ZE	100% ZE
N2 – Lichte vrachtwagens	EURO 4	EURO 4	EURO 6	100% ZE
N3 – Zware vrachtwagens M2/M3 – Bussen	EURO 4	EURO 4	EURO 6	EURO 6