

The technical drawing illustrates the mast assembly EUO 0.4 60 1200/5-PTU60. It includes a side view with dimensions: total length 1200, mounting height 400 (split into 240 and 60), and a 5° tilt. Key components are labeled 1 through 5. A detail view shows a 120° (3x) flange. A 3D perspective view shows the mast's L-shaped profile. A parts list table is provided below the drawing.

Pos	Aant.	Artikelnummer	Omschrijving	Breed	Lang	Art. Nr.	Grnd.
5	1	04040700005	Dop f-5 gpn300 inw.Ø 10,7				
4	6	01100312025	Tapbout M12x25 RVS A2 din933				
3	1	7071154002	Deksel Ø71x3	71	71	08201400003	
2	1	E000043813	Buis 60,3x2,9 S235JR L=6mtr.		1188	08010806003	
1	1	7091804030	Opzetstuk 76-60-1-400 met LM				

TOLERANTIES		VOORBEHANDELINGSGRAAD		UITVOERINGSKLASSE		KWALITEITSNIVEAU LASSEN	
Lichtmasten: NEN-EN 40-2, Overige masten: NEN-EN 1090-2, Algemeen: NEN-EN ISO 13920 - klasse C/G		Producten geschikt voor thermisch verzinken : NEN-EN ISO 8501 - klasse P1		Lichtmasten: NEN-EN 40-5 - Geen klasse, Overige masten: NEN-EN 1090 - klasse EXC 2		NEN-EN ISO 5817 klasse C	

Omschrijving:		Project/Memo:		Doc.nr.:	
EUO 0.4 60 1200/5-PTU60				6273353001.dwg	
				Art.nr.: 6273353001.iam	

Getekend:	Status:	Schaal:	Formaat:	Specificatie nummer:	Rev.:
18-Jun-13	Voor productie	1:5	A3	6273353001	C