

Minimale wanddikte / aantal glaslagen Lokale reparaties

Materiaal: glasvezel

Oppervlaktegewicht: minimaal 1300 g/m²

Diameter	Minimale wanddikte	
DN 200	2 glaslagen	3,0 mm
DN 250	2 glaslagen	3,0 mm
DN 300	3 glaslagen	4,5 mm
DN 400	3 glaslagen	4,5 mm
DN 500	4 glaslagen	6,0 mm
DN 600	4 glaslagen	6,0 mm
DN 700	5 glaslagen	9,0 mm
DN 800	5 glaslagen	9,0 mm
DN 900	5 glaslagen	9,0 mm
DN 1000	5 glaslagen	9,0 mm

250/375	3 glaslagen	4,5 mm
300/450	3 glaslagen	4,5 mm
350/525	4 glaslagen	6,0mm
400/600	4 glaslagen	9,0 mm
500/750	4 glaslagen	9,0 mm
600/900	5 glaslagen	9,0mm