

1. Applicable to

Artificial Turf Filament, in different colours

2. Base Polymer

Polypropylen (PP)

3. Characteristics

shape:	ridged film profile
number of filaments	6
HALS:	uv protected
finish:	3,5 rpm at 6 %
wrapping:	48 wraps per meter



3. typical values of physical properties

titer:	6,600 dtex (6 Filaments)
width:	1.3 mm
thickness:	120 μ m
strength (F max) (single strand)	> 20 N
elongation (at break):	40 %
shrinkage (Testrite):	0,5 %