

Projectnummer: 222936
Projectomschrijving: Fase 5 Voorbelasting
Projectleider: Danny Oltmans
Opdrachtgever: Braassemmerland V.O.F.
Contactpersoon:

Datum: 16-12-2025
Versie: 2.0

Grondbalans: AdB222936-2

Grond ontgraven				
bestekspost	ontgraven	vervoeren	Op kant	direct verwerken
212010	875	875		
212020	1430	1430		
213010	1630	1630		
213020	45	45		
215010	18000	10100		
		7900		
231510	3340	875		
		1430		
		1035		
231520	32365	4950		
		12670		
		4425		
		320		
		10000		

57685 57685 0 0

57685 → 57685

57685 → 57685 → 25705 → 25705

Grond vervoeren					
bestekspost	vervoer binnen werk	vervoer binnen werk	vervoer binnen werk	vervoer uit schip	vervoer uit schip
221010	875				
	1430				
221020		1630			
		45			
215020			10100		
			7900		
231610				875	
				1430	
				1035	
231620					4950
					12670
					4425
					320
					10000

2305 1675 18000 3340 32365

Grond verwerken			
bestekspost	verwerken	levering + verwerken	verwerken levering
231010		875	875
231020		1430	1430
231030	10100		
231040		4950	4950
231050	7900	12670	12670
231060		4425	4425
231070		320	320
231080	10000		
232010	2305	1035	1035
	1675		

31980 25705 25705

Grond leveren	
levering	bestekspost
875	231110
1430	231110
4950	231120
12670	231120
4425	231120
320	231120
1035	231110

25705