


## Art.no. 84451-20001

EAN 7316911401137



**Touch** is a stylish and timeless luminaire that will fit smoothly into any retail environment. The integrated driver gives clean feeling and the shop ceiling will not be cluttered with drivers aimed in different directions.

**Installation** Track mounted 3-phase track, Control track or iTrack.

**Design** Housing in powder coated aluminium, white (RAL 9016) or black (RAL 9017). Integrated driver.

**Dimming** DALI/phase pulse control.

**Miscellaneous** 930 LED is Below Black Body Locus (BBBL), other colour temperature on Black Body Locus.

## Touch Midi G2

Medium Beam, 3-phase track, On/off, LL

### DESIGN

<b>Installation</b> 3-phase track	<b>Light distribution</b> Medium Beam
<b>Beam angle, °</b> 20	<b>Tilt, °</b> 90
<b>Turn, °</b> 360	<b>Colour</b> White

### LIGHT DATA & PERFORMANCE

<b>Lumen output</b> 3761	<b>lm/W</b> 123
<b>CCT, K</b> 3000 BBBL	<b>CRI</b> 90
<b>SDCM</b> 3	<b>Lumen maintenance 35 000 h</b> L95
<b>Lumen maintenance 50 000 h</b> L93	<b>Lumen maintenance 75 000 h</b> L89
<b>Lumen maintenance 100 000 h</b> L86	<b>LED driver, h/max failure %</b> 100000/10
<b>Energy class, LED module</b> E	

### CONTROLS & CONNECTIVITY

<b>Light control</b> On/off	<b>Driver brand</b> Philips
<b>ZD4i Certified</b> False	<b>Daylight functionality</b> False

### ELECTRICITY & ENCLOSURE

<b>Rated supply voltage, V</b> 220-240	<b>Mains frequency, Hz</b> 50, 60
<b>Protective class</b> 2	<b>IP rating</b> 20
<b>System Wattage</b> 31	<b>Min. ambient temperature, °C</b> -20
<b>Max. ambient temperature, °C</b> 25	<b>MCB B10A, pcs</b> 18
<b>MCB B16A</b> 30	<b>MCB C10A</b> 31
<b>MCB C16A</b> 52	<b>THD, %</b> 8
<b>Surge protection CM, kV/kA</b> 2	<b>Surge protection DM, kV/kA</b> 1
<b>Power factor, 100 %</b> 0.97	<b>NTC function</b> False

### DIMENSIONS

<b>Length, mm</b> 117	<b>Width, mm</b> 135
<b>Height, mm</b> 222	<b>Diameter, mm</b> 117
<b>Weight, kg</b> 1	