

BIJLAGE 10.4a
CONSERVERING SPECIFICATIE 50 en 60 SCHEPEN



CONSERVERING IJVEREN 50 EN 60 SERIE			
Laag	Product	Kleur	Laagdikte
Accommodatie en opbouwen			
1	Sigmacover 280	Greenish yellow	75 mμ
2	Sigmacover 456	Light grey	100 mμ
3	Sigmacover 456	Off white	100 mμ
4	Sigmadur 550	White Sigma 3819-5	75 mμ
Machinekamer en technische ruimte			
1	Sigmacover 280	Greenish yellow	75 mμ
2	Sigmacover 456	Off white	100 mμ
3	Sigmadur 550	White 7000	50 mμ
Verschansing binnen & buitenkant			
1	Sigmacover 280	Greenish yellow	75 mμ
2	Sigmacover 456	Grey	100 mμ
3	Sigmacover 456	Off white	100 mμ
4	Sigmadur 550	Blue Ral 5017	75 mμ
Onderwater gedeelte			
1	Sigmacover 280	Greenish yellow	75 mμ
2	Sigmashield 420 (grey)	Grey	200 mμ
3	Sigmacover 525	Black	75 mμ
4	Ecofleet 530	Brown	100 mμ
5	Ecofleet 530	Red-brown	100 mμ
Topside (waterlijn tot aan de berghoutsgang)			
1	Sigmacover 280	Greenish yellow	75 mμ
2	Sigmashield 420	Grey	125 mμ
3	Sigmacover 456	Grey	75 mμ
4	Sigmadur 550	Blue Ral 5013	75 mμ

BIJLAGE 10.4a
CONSERVERING SPECIFICATIE 50 en 60 SCHEPEN



CONSERVERING IJVEREN 50 EN 60 SERIE			
Passagiersdek			
1	Sigmacover 280	Greenish yellow	75 mμ
2	Sigmacover 280	Greenish yellow	75 mμ
3	Sigmacover 456	Light grey	100 mμ
4		Light grey (RAL 7015)	Instrooien
5	Sigmacover 456	Grey RAL 7015	100 mμ
Stuurhut -en topdek			
1	Sigmacover 280	Greenish yellow	75 mμ
2	Sigmacover 456	Light grey	100 mμ
3		Light grey (RAL 7030)	Instrooien
4	Sigmacover 456	Grey RAL 7030	100 mμ
Wachtruimte			
1	Sigmacover 280	Greenish yellow	75 mμ
2	Sigmacover 456	Light grey	100 mμ
3	Sigmadur 550	Blue (Ral 5023)	75 mμ
Ballasttanks, voor -en achterpiek			
1	Sigmacover 380	Greenish yellow	160 mμ
2	Sigmacover 380	Grey	160 mμ
Droge tanks			
1	Sigmacover 380	Grey	160 mμ