

BIJLAGE 10.4b
CONSERVERING SPECIFICATIE 100 SCHEPEN



CONSERVERING NZK PONTEN 100 SERIE			
Laag	Product	Kleur	Laagdikte
Accommodatie en opbouwen			
1	Sigmacover 280	Greenish yellow	75 mμ
2	Sigmacover 420	Grey	100 mμ
3	Sigmacover 456	Off white	100 mμ
4	Sigmadur 550	White Sigma 3819-5	75 mμ
Machinekamer en technische ruimte			
1	Sigmacover 280	Greenish yellow	75 mμ
2	Sigmacover 456	Off white	100 mμ
3	Sigmadur 550	White 7000	50 mμ
Verschansing binnen & buitenkant			
1	Sigmacover 280	Greenish yellow	75 mμ
2	Sigmashield 420	Grey	100 mμ
3	Sigmacover 456	Off white	100 mμ
4	Sigmadur 550	Blue Ral 5017	75 mμ
Onderwater gedeelte			
1	Sigmacover 280	Greenish yellow	75 mμ
2	Sigmashield 420	Grey	200 mμ
3	Sigmacover 555	Black	75 mμ
4	Ecofleet 530	Brown	100 mμ
5	Ecofleet 530	Red-brown	100 mμ
Topside (waterlijn tot aan de berghoutsgang)			
1	Sigmacover 280	Greenish yellow	75 mμ

CONSERVERING NZK PONTEN 100 SERIE			
Laag	Product	Kleur	Laagdikte
2	Sigmashield 420	Grey	125 mμ
3	Sigmacover 456	Grey	75 mμ
4	Sigmadur 1800	Blue Ral 5013	75 mμ
Onder pass. kleppen, voor -en achtersteven (spiegels)			
4	Sigmadur 1800	Black	75 mμ
Passagiersdek			
1	Sigmacover 280	Greenish yellow	75 mμ
2	Special coating by Herculon (RAL 7015)		
Stuurhut -en topdek			
1	Sigmacover 280	Greenish yellow	75 mμ
2	Sigmacover 456	Light grey	100 mμ
3		Light grey (RAL 7030)	Instrooien
4	Sigmacover 456	Grey RAL 7030	100 mμ
Ballasttanks, voor -en achterpiek			
1	Sigmacover 380	Greenish yellow	160 mμ
2	Sigmacover 380	Grey	160 mμ
Droge tanks			
1	Sigmacover 380	Grey	160 mμ