

Districttotaal

Locatie ca.	Situatie				
N-wegnr.	voetpad, abri, rabatstrook e.d.* in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
N199	5.170	3.405	620	7.265	810
N221	3.374	1.866	340	11.198	0
N224	5.061	3.458	115	8.283	1.219
N225	58.556	3.067	67	14.977	1.442
N226	5.493	3.533	64	8.856	223
N227	6.072	6.589	264	12.574	507
N229	4.185	7.193	32	7.461	1.659
N233	10.735	4.983	144	9.478	960
N234	395	3.213	0	7.474	560
N237	32.657	3.322	1.500	37.643	940
N238	2.195	2.305	60	1.850	1.140
N410	59	2.199	0	1.067	0
N411	1.742	1.424	8	1.672	0
N412	282	834	16	1.974	612
N413	800	2.415	44	400	960
N414	480	1.580	0	1.460	0
N415	628	1.945	110	578	0
N416	811	125	0	940	0
N417	3.086	2.446	0	8.633	0
N806	1.000	130	0	1.200	0
Totaal	142.781	56.032	3.384	144.983	11.032

Totaal vierkante meters	202.197 m2
Totaal strekkende meters band/leicon	144.983 m1
Totaal strekkende meters goot	11.032 m1

*e.d: weinig bereiden straatwerk, bushaltes, parkeervakken,
en overige locaties waar onkruid op de verharding aanwezig is.

N199

Locatie ca.		Situatie				
N-wegnr.		voetpad, abri, rabatstrook e.d. in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
0,30	1,00	480	890	20	1.425	250
1,00	2,00	130	200	80	390	
2,00	3,00	910	339	60	1.320	
3,00	4,00	1.350	988		1.800	60
4,00	5,00	1.250	738	30	1.340	
5,00	6,00	600	100	240	570	
6,00	7,00	450	150	140	420	300
7,00	7,50			50		200
Weg totaal N199		5.170	3.405	620	7.265	810

N221

Locatie ca.		Situatie				
N-wegnr.		voetpad, abri, rabatstrook e.d. in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
0,00	0,540	165	225		560	
32,450	33,100		760		943	
33,100	33,650	500	375		483	
33,650	34,200		120		2.274	
34,200	34,700	600	230		2.055	
34,700	35,200	699	96	18	1.140	
35,200	35,700	345	60	171	803	
35,700	36,300	286		70	1.360	
36,300	36,820	779		81	1.580	
Weg totaal N221		3.374	1.866	340	11.198	0

N224

Locatie ca.		Situatie				
N-wegnr.		voetpad, abri, rabatstrook e.d. in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
4,000	4,400	349	183		438	223
4,800	5,100	551	70		200	
5,100	6,000	135				
6,400	6,800	366				
7,200	7,500				450	
7,800	8,200	422		20	390	
8,700	8,800	187				
8,900	10,400	61	60	8	191	402
10,400	11,400	44	50		413	
11,500	12,500		330	39		
12,500	13,000	484	796		1.136	388
13,300	13,400		380		276	
13,600	13,800		30		186	120
14,200	14,400		43		86	
15,100	16,400	263	170		2.470	86
16,600	16,700	9			302	
21,000	22,000	75		48		
22,000	23,000	888	801		1.058	
23,000	24,000	1.187	545		644	
24,800	25,400	40			43	
Weg totaal N224		5.061	3.458	115	8.283	1.219

N225

Locatie ca.		Situatie				
N-wegnr.		voetpad, abri, rabatstrook e.d. in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
16,000	17,700	1.172	589	3	83	89
17,700	19,150	1.607	430	10	555	0
20,600	21,000	0	62	0	94	0
21,000	22,000	14	253	12	122	0
22,000	23,000	18	290	0	22	0
23,000	24,000	383	198	22	147	0
24,000	25,400	0	160	0	0	0
25,000	26,000	6.702	147	0	1.491	128
26,000	27,000	9.290	136	0	2.501	0
27,000	28,000	4.260	34	0	1.391	151
28,000	29,040	4.615	194	0	2.293	0
29,040	30,000	3.334	184	0	1.795	0
30,000	31,000	338	65	0	0	797
31,000	32,000	2.766	34	0	65	0
32,000	33,000	3.191	43	0	1.383	0
33,000	34,000	4.764	18	0	2.021	0
34,000	35,000	2.724	0	0	0	0
35,000	36,000	2.619	16	12	86	0
36,000	37,245	3.512	0	0	0	0
39,100	40,200	6.702	204	0	862	277
41,200	42,000	445	10	0	38	0
42,000	42,700	100	0	8	28	0
Weg totaal		58.556	3.067	67	14.977	1.442

N226

Locatie ca.		Situatie				
N-wegnr.		voetpad, abri, rabatstrook e.d. in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
49,065	49,700	50	82	9	428	
49,200	49,300	100			100	
50,400	50,800	534	58		293	68
51,100	51,200			7		
51,400	51,800	789	87		547	
52,600	52,900	41	13	6	144	
53,600	53,900	35			35	
54,900	55,000	47			34	
55,300	55,900	259	300		604	
55,500	57,000	2.900	854		4.115	
57,000	58,100	21	307	19	196	
58,000	58,800	658	50	20	828	155
58,800	59,200	59	320		920	
59,200	60,300		482	3	462	
60,550	61,400		40		65	
61,100	61,250				24	
61,400	62,000		150		24	
62,000	63,100		790		42	
Weg totaal N226		5.493	3.533	64	8.856	223

N227

Locatie ca.		Situatie				
N-wegnr.		voetpad, abri, rabatstrook e.d. in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
-0,092	0,300	2.026	271	67	3.379	215
0,400	0,900		490		429	
1,500	1,800		507		647	
2,500	2,700				56	
3,090	3,400	403		35		
3,600	3,800				49	
4,600	5,000	33	450		801	
5,200	6,600	312	670		1.540	
6,700	7,200		90		6	
7,200	8,800	86	1.797	18	2.401	
8,800	9,300	31	90		26	
9,300	10,200	31	159		148	
12,000	12,900	280	230	63	92	
12,900	13,500	261	575	6	92	
13,500	15,100	1.984	1.000	2	2.878	292
15,100	15,600		240		30	
15,600	15,900	625	20	73		
Weg totaal N227		6.072	6.589	264	12.574	507

N229

Locatie ca.		Situatie				
N-wegnr.		voetpad, abri, rabatstrook e.d. in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
5,750	6,800	639	1.555		1.742	
6,800	7,300	211	586		530	
7,300	7,850		40			88
7,600	8,450	377	786		554	
8,450	9,000	353	475		48	
9,000	10,100		912		518	
10,100	11,150	472	185		88	
11,150	11,700		60		31	
12,000			20		23	
12,200	12,800		70		34	
12,800	13,100				785	238
13,350	14,400	121	190	7	68	
14,100	14,800		155	16		
14,900	15,500	18	324	7	203	
15,600	16,000	50	415		22	
15,860	16,300	1.944	725		938	
16,000	16,550		55		159	159
16,500	17,100		50		59	
16,800	17,400				613	613
17,100	17,700		45		197	197
17,600	17,800		290	2	485	
17,700	18,300		255		364	364
Weg totaal N229		4.185	7.193	32	7.461	1.659

N233

Locatie ca.		Situatie				
N-wegnr.		voetpad, abri, rabatstrook e.d. in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
1,200	1,855	1.692	814		1.564	107
		Oostelijke Rondweg Veenendaal				
1,450	1,750		20		628	
1,950	2,250				248	
2,300	2,450	290			44	
2,940	3,300		590	27	750	195
4,000	5,000	21	2.011		2.300	193
5,000	6,000			90		345
6,000	7,000	1.810	728	11	888	
7,000	8,000	955	31		266	
8,000	9,000	2.348	239	6	888	
9,000	10,000	1.089			177	
10,000	11,000	143	98		424	
11,000	11,700	1.461	273	10	1.048	120
ORV	Gem. Gr.	926	179		253	
Weg totaal N233		10.735	4.983	144	9.478	960

N234

Locatie ca.		Situatie				
N-wegnr.		voetpad, abri, rabatstrook e.d. in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
0,00	11,36	395			3.737	280
0,00			88			
0,15			75			
0,25			170			
6,60			140			
2,30			110			
3,60	3,90		990			
4,70	4,90		320			
5,30	5,55		750			
6,10			60			
6,25			160			
7,50			130			
8,45			60			
9,72			160		3.737	280
Weg totaal N234		395	3.213	0	7.474	560

N237

Locatie ca.		Situatie				
N-wegnr.		voetpad, abri, rabatstrook e.d. in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
72,90	74,00	2.977	480	60	6.814	
74,00	75,00	4.580	815	0	6.665	
75,00	76,00	2.090	440	120	4.030	100
76,00	77,00	320	0	100	2.250	
77,00	80,00	830	30	310	1.970	
80,00	81,00	1.570	50	200	1.400	
81,00	82,00	2.580	70	210	2.950	260
82,00	83,00	2.010	0	200	2.640	
83,00	84,00	755	50	80	2.900	
84,00	85,00	2.470	1.300	200	4.750	100
85,00	86,00	3.785	75	20	370	
86,00	87,00	3.700	12		174	
87,00	88,00	3.950	0		650	180
88,00	88,30	1.040	0		80	300
Weg totaal N237		32.657	3.322	1.500	37.643	940

N238

Locatie ca.		Situatie				
N-wegnr.		voetpad, abri, rabatstrook e.d. in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
0,00	6,54	2.195		60	1.850	1.140
1,30			90			
1,80			105			
2,40	2,50		90			
2,80			120			
3,65			120			
4,80	5,10		730			
5,44			20			
5,50	5,65		585			
6,10			180			
6,47	6,54		265			
Weg totaal N238		2.195	2.305	60	1.850	1.140

N410

Locatie ca.		Situatie				
N-wegnr.		voetpad, abri, rabatstrook e.d. in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
0,100	1,200	3	650		121	
1,200	1,700	6	355		234	
1,700	2,400	44	475		427	
2,500	3,000	3	170		123	
3,000	3,600	3	220		123	
3,600	4,200		329		39	
Weg totaal N410		59	2199	0	1.067	0

N411

Locatie ca.		Situatie				
N-wegnr.		voetpad, abri, rabatstrook e.d. in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
0,700	2,200	623	490	8	698	
2,000	3,200	91	210		290	
3,000	4,150	1.028	724		684	
Weg totaal N411		1.742	1.424	8	1.672	0

N412

Locatie ca.		Situatie				
N-wegnr.		voetpad, abri, rabatstrook e.d. in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
0,00	5,00	75	294		360	592
0,50	1,00	130	440	16	1.120	20
1,00	1,40	77	100		494	
Weg totaal N412		282	834	16	1.974	612

N413

Locatie ca.		Situatie				
N-wegnr.		voetpad, abri, rabatstrook e.d. in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
0,00	5,28	800		44	400	960
0,30	0,70		1.200			
0,55			100			
1,00	1,25		875			
1,30			120			
3,98	4,10		120			
Weg totaal N413		800	2.415	44	400	960

N414

Locatie ca.		Situatie				
N-wegnr.		voetpad, abri, rabatstrook e.d. in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
0,49	5,61	480			1.460	
0,49	0,55		90			
0,70	0,95		1.400			
1,27			60			
5,17			30			
Weg totaal N414		480	1.580	0	1.460	0

N415

Locatie ca.		Situatie				
N-wegnr.		voetpad, abri, rabatstrook e.d. in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
1,43	5,44			110		
1,43	1,50	108	238		111	
3,00	3,50		279			
3,50	3,90	100	143		100	
3,90	4,30	246	1.085		267	
5,39	5,44	174	200		100	
Weg totaal N415		628	1.945	110	578	0

N416

Locatie ca.		Situatie				
N-wegnr.		voetpad, abri, rabatstrook e.d. in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
0,000	0,500	685	61		594	
2,300	2,500	98			21	
3,200	3,600	28	64		325	
Weg totaal N416		811	125	0	940	0

N417

Locatie ca.		Situatie				
N-wegnr.		voetpad, abri, rabatstrook e.d. in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
4,000	4,180				660	
4,540	4,720		39		180	
4,720	5,000	297	105		480	
5,000	6,000	566	325		2.169	
6,000	6,700	420	599		2.319	
6,700	7,200	138	267		1.000	
7,200	7,800	900	748		975	
7,800	8,300	765	363		850	
Weg totaal N417		3.086	2.446	0	8.633	0

N806

Locatie ca.		Situatie				
N-wegnr.		voetpad, abri, rabatstrook e.d. in m2	middengeleider in/uitritten in m2	kolk-ombouw in m2	band/leicon in m1	goot in m1
0,00	1,95	1.000			1.200	
0,50	0,60		80			
1,65			50			
Weg totaal N806		1.000	130	0	1.200	0